

**ओरिएण्टल
इंश्योरेंस**

पृथ्वी, अग्नि, जल, आकाश। सबकी सुरक्षा हमारे पास।
www.orientalinsurance.nic.in * बीमा आग्रह की विषय वस्तु है।



**Oriental
insurance**

Prithvi, Agni, Jal, Aakash. Sab ki suraksha hamare paas.
www.orientalinsurance.nic.in *Insurance is the subject matter of solicitation.

**THE ORIENTAL INSURANCE COMPANY LIMITED
(A GOVT OF INDIA UNDERTAKING)**

REQUEST FOR PROPOSAL

For

**Elevation of Pavement, Water Proofing on Canopy
Terrace & Painting Work of Canopy Ceiling outside
H.O. Building at A-25/27, Asaf Ali Road New Delhi**

Tender No. : HO/Estate/2018/06

**CHIEF MANAGER
ESTATE DEPARTMENT
HEAD OFFICE "ORIENTAL HOUSE"
A-25/27, ASAF ALI ROAD, NEW DELHI-110002**

**PART –II
FINANCIAL BID**

Submitted by:

Signature: _____

Name: _____

Contact No.: _____



Section – VII Schedule of Quantities

- i. Rates are for working at all heights including cost of centering shuttering and scaffolding.
- ii. Wherever BASIC PRICES are mentioned in Specifications, they shall be exclusive of GST and transportation, loading, unloading, breakages etc.
- iii. Rates include disposal of rubbish pertaining to dismantling to all leads and lifts.

S NO	ITEM / WORKS	SPECIFICATIONS	UNITS	QTY	BASIC RATES IN WORDS	BASIC RATES IN FIGURES	AMOUNT	TOTAL
A	CIVIL WORK							
1	Dismantling and Disposal of malba Work	Dismantling of existing rcc work, including mosaic flooring, kota stone , cement plaster ,cutting of reinforcement, electrical fixtures/fitting and disposal of material / mulba as directed to municipal dumping ground	LS	1.00				
2	P.C.C.	Providing and laying all kind of Plain cement concrete (1:4:8) in lintels, beams, slabs, sunshade, column, foundation, footings, under lay of flooring counter shelves, including leaving cutouts, excluding shuttering, etc., at all heights & levels, complete as per IS including curring for seven days	CUM	55.00				
3	Brick work 9"	brick work with common burnt clay bricks Of class designation 7.5 in steps using cement mortar 1: 4	CUM	1.00				
4	Brick work 4.5"	brick work with common burnt clay bricks Of class designation 7.5 in steps using cement mortar 1: 4	SMT	2.00				
5	Cement plaster	New plaster in regular shape in mortar 12mm to 25 mm thk 1:4 (1 cement:4 sand) 50% of river/fine sand 50% coarse sand) including mixing of admixed Dr. Fixit Pidiproof LW+. Dr. Fixit Pidifin 2K including scaffolding, etc, complete all level.	SMT	2.00				



6	Water Proofing	WATER PROOFING WORK SURFACE PREPRATION FOR ALL TERRACE AREA of conopy Through cleaning of the entire roof by chipping, wire brushing, coir brushing, brooming followed by water cleaning to get a sound surface free of dust, dirt, laitance and any other foreign materials Cutting "V" shape groove along the junction of roof and parapet walls only plus cracks if found and cleaning the same with water. Thereafter sealing the same with polymer modified mortar with Dr Fixit URP mixed with sand cement mortar / concrete @ 8-10 % by weight of cement over a bonding cum waterproofing coat with 1 part of Dr Fixit URP mixed with 2 parts cement.	SMT	350.00				
7	kerb stone	Providing and laying at or near ground level factory made kerb stone of M- 25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	cum	5.00				
8	New Kota stone	Providing and fixing Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) :	SMT	350.00				
B	PAINTING WORK							
1	ENAMEL PAINT WORKS	Providing and apply 2 or more coats of enamel paint of approved make including cleaning and rubbing of old surfaces with emery paper of appropriatr grade	SMT	1.00				



2	OBD	Applying and Painting with OBD paint of approved brand and manufacturer and of required shade on old / new surface three or more coats to give an even shade including necessary surfacing putty, filling and application of 1 coat of primer, after thoroughly preparing the surface. etc.	SMT	350.00				
	TOTAL COST OF THE WORKS							
	TOTAL COST OF THE WORKS (in words)							

(The tenderer shall quote in figures and in words)

NOTE:- GST as applicable, on works contract, shall be paid extra on above quoted Prices.

Submitted by:

Signature : _____

Name : _____

Contact No. : _____

Contractor's Stamp: _____